

Welcome to **E-XFL.COM** 

What is "Embedded - Microcontrollers"?


"Embedded - Microcontrollers" refer to small, integrated circuits designed to perform specific tasks within larger systems. These microcontrollers are essentially compact computers on a single chip, containing a processor core, memory, and programmable input/output peripherals. They are called "embedded" because they are embedded within electronic devices to control various functions, rather than serving as standalone computers. Microcontrollers are crucial in modern electronics, providing the intelligence and control needed for a wide range of applications.

Applications of "<u>Embedded - Microcontrollers</u>"

Details	
Product Status	Active
Core Processor	AVR
Core Size	8-Bit
Speed	20MHz
Connectivity	I <sup>2</sup> C, SPI, UART/USART
Peripherals	Brown-out Detect/Reset, POR, PWM, WDT
Number of I/O	32
Program Memory Size	32KB (16K x 16)
Program Memory Type	FLASH
EEPROM Size	1K x 8
RAM Size	2K x 8
Voltage - Supply (Vcc/Vdd)	1.8V ~ 5.5V
Data Converters	A/D 8x10b
Oscillator Type	Internal
Operating Temperature	-40°C ~ 85°C (TA)
Mounting Type	Surface Mount
Package / Case	44-TQFP
Supplier Device Package	44-TQFP (10x10)
Purchase URL	https://www.e-xfl.com/product-detail/microchip-technology/atmega324a-au

#### Pinout - DRQFN for Atmel ATmega164A/164PA/324A/324PA 1.2

Figure 1-2. DRQFN - pinout.




DRQFN - pinout. **Table 1-1.** 

A1	PB5	A7	PD3	A13	PC4	A19	PA3
B1	PB6	B6	PD4	B11	PC5	B16	PA2
A2	PB7	A8	PD5	A14	PC6	A20	PA1
B2	RESET	B7	PD6	B12	PC7	B17	PA0
A3	VCC	A9	PD7	A15	AVCC	A21	VCC
В3	GND	B8	VCC	B13	GND	B18	GND
A4	XTAL2	A10	GND	A16	AREF	A22	PB0
B4	XTAL1	В9	PC0	B14	PA7	B19	PB1
A5	PD0	A11	PC1	A17	PA6	A23	PB2
B5	PD1	B10	PC2	B15	PA5	B20	PB3
A6	PD2	A12	PC3	A18	PA4	A24	PB4



# 2.1 Block diagram

Figure 2-1. Block diagram.



The AVR core combines a rich instruction set with 32 general purpose working registers. All the 32 registers are directly connected to the Arithmetic Logic Unit (ALU), allowing two independent registers to be accessed in one single instruction executed in one clock cycle. The resulting architecture is more code efficient while achieving throughputs up to ten times faster than conventional CISC microcontrollers.

The Atmel ATmega164A/164PA/324A/324PA/644A/644PA/1284P provide the following features:

16/32/64/128Kbytes of In-System Programmable Flash with Read-While-Write capabilities, 512/1K/2K/4Kbytes EEPROM, 1/2/4/16Kbytes SRAM, 32 general purpose I/O lines, 32 general purpose working registers, Real Time Counter (RTC), three (four for ATmega1284/1284P) flexible Timer/Counters with compare modes and PWM, 2 USARTs, a byte oriented two-wire Serial Interface, a 8-channel, 10-bit ADC with optional differential input stage with programmable gain, programmable Watchdog Timer with Internal Oscillator, an SPI serial port, IEEE std. 1149.1 compliant JTAG test interface, also used for accessing the On-chip Debug system and programming and six software selectable power saving modes. The Idle mode stops the CPU while allowing the SRAM, Timer/Counters, SPI port, and interrupt system to continue functioning. The Power-down mode saves the register contents but freezes the Oscillator, disabling all other chip functions until the next interrupt or Hardware Reset. In Power-save mode, the asynchronous timer continues to run, allowing the user to maintain a



timer base while the rest of the device is sleeping. The ADC Noise Reduction mode stops the CPU and all I/O modules except Asynchronous Timer and ADC, to minimize switching noise during ADC conversions. In Standby mode, the Crystal/Resonator Oscillator is running while the rest of the device is sleeping. This allows very fast start-up combined with low power consumption. In Extended Standby mode, both the main Oscillator and the Asynchronous Timer continue to run.

Atmel offers the QTouch<sup>®</sup> library for embedding capacitive touch buttons, sliders and wheels functionality into AVR microcontrollers. The patented charge-transfer signal acquisition offers robust sensing and includes fully debounced reporting of touch keys and includes Adjacent Key Suppression<sup>®</sup> (AKS™) technology for unambiguous detection of key events. The easy-to-use QTouch Suite toolchain allows you to explore, develop and debug your own touch applications.

The device is manufactured using Atmel's high-density nonvolatile memory technology. The On-chip ISP Flash allows the program memory to be reprogrammed in-system through an SPI serial interface, by a conventional nonvolatile memory programmer, or by an On-chip Boot program running on the AVR core. The boot program can use any interface to download the application program in the application Flash memory. Software in the Boot Flash section will continue to run while the Application Flash section is updated, providing true Read-While-Write operation. By combining an 8-bit RISC CPU with In-System Self-Programmable Flash on a monolithic chip, the Atmel ATmega164A/164PA/324A/324PA/644A/644PA/1284/1284P is a powerful microcontroller that provides a highly flexible and cost effective solution to many embedded control applications.

The ATmega164A/164PA/324A/324PA/644A/644PA/1284/1284P is supported with a full suite of program and system development tools including: C compilers, macro assemblers, program debugger/simulators, in-circuit emulators, and evaluation kits.

# 2.2 Comparison between ATmega164A, ATmega164PA, ATmega324A, ATmega324PA, ATmega644A, ATmega644PA, ATmega1284 and ATmega1284P

Table 2-1. Differences between ATmega164A, ATmega164PA, ATmega324PA, ATmega324PA, ATmega644A, ATmega644PA, ATmega1284 and ATmega1284P.

	<u> </u>			
Device	Flash	EEPROM	RAM	Units
ATmega164A	16K	512	1K	
ATmega164PA	16K	512	1K	
ATmega324A	32K	1K	2K	
ATmega324PA	32K	1K	2K	hytaa
ATmega644A	64K	2K	4K	bytes
ATmega644PA	64K	2K	4K	
ATmega1284	128K	4K	16K	
ATmega1284P	128K	4K	16K	

# 2.3 Pin Descriptions11

#### 2.3.1 VC

Digital supply voltage.

#### 2.3.2 GND

Ground.



#### 3. Resources

A comprehensive set of development tools, application notes and datasheets are available for download on http://www.atmel.com/avr.

# 4. About code examples

This documentation contains simple code examples that briefly show how to use various parts of the device. Be aware that not all C compiler vendors include bit definitions in the header files and interrupt handling in C is compiler dependent. Please confirm with the C compiler documentation for more details.

The code examples assume that the part specific header file is included before compilation. For I/O registers located in extended I/O map, "IN", "OUT", "SBIS", "SBIC", "CBI", and "SBI" instructions must be replaced with instructions that allow access to extended I/O. Typically "LDS" and "STS" combined with "SBRS", "SBRC", "SBR", and "CBR".

#### 5. Data retention

Reliability Qualification results show that the projected data retention failure rate is much less than 1 PPM over 20 years at 85°C or 100 years at 25°C.

# 6. Capacitive touch sensing

The Atmel QTouch Library provides a simple to use solution to realize touch sensitive interfaces on most Atmel AVR microcontrollers. The QTouch Library includes support for the QTouch and QMatrix acquisition methods.

Touch sensing can be added to any application by linking the appropriate Atmel QTouch Library for the AVR Microcontroller. This is done by using a simple set of APIs to define the touch channels and sensors, and then calling the touch sensing API's to retrieve the channel information and determine the touch sensor states.

The QTouch Library is FREE and downloadable from the Atmel website at the following location: www.atmel.com/qtouchlibrary. For implementation details and other information, refer to the Atmel QTouch Library User Guide - also available for download from the Atmel website.



BOSCO    UCSRIAN   ROCCO   TACK   UCSRIAN   FEB   DOMB   UFED   USDO   RF-DAN   TREATS	Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Page
(GREPT   Reserved	(0xC0)	UCSR0A	RXC0	TXC0	UDRE0	FE0	DOR0	UPE0	U2X0	MPCM0	185/200
(GRIG)   TWORK   TWO	(0xBF)	Reserved	-		-	-	-	-	-	-	
General   Tourist	(0xBE)	Reserved	-	-	-	-	-	-	-	-	
Design   TOUR	(0xBD)	TWAMR	TWAM6	TWAM5	TWAM4	TWAM3	TWAM2	TWAM1	TWAM0	-	231
General   TWAR	(0xBC)	TWCR	TWINT	TWEA	TWSTA	TWSTO	TWWC	TWEN	-	TWIE	228
Decision   TWSR   TWSP   TWS						1		1		•	
(0.68)   (	, ,	+		+	1	<b>+</b>	<b>+</b>			+	
Code	<del></del>		TWS7	TWS6	TWS5				TWPS1	TWPS0	
Godes   ASSR	· · · · · ·						1	t Rate Register			228
		+						-			455
1969    OCR26								OCR2BUB			155
GNR3    GORRA			-	-	-			nare Pegister B	-	-	155
COMPAIN   TOCRES   FOCAS   FOCAS   FOCAS   FOCAS   CSSS   CSSS	· · · · · ·						•				
Gost   Gorgan   Gor		1									
TOCREA			FOC2A	FOC2B	-				CS21	CS20	
DAMP    Reserved			1							+	+
GWAP    Reserved	<del></del>						-	-			
(0)AC) Reserved	(0xAE)	Reserved	-	-	-	-	-	-	-	-	
(DuAB)   Reserved			-	-	-	-	-	-	-	-	
Dischard   Reserved	(0xAC)	Reserved	-	-	-	-	-	-	-	-	
(DAM)   Reserved	(0xAB)	Reserved	-	-	-	-	-	-	-	-	
(0xA9) Reserved	(0xAA)	Reserved	-	-	-	-	-	-	-	-	
(0xAr)   Reserved   -	(0xA9)	Reserved	-	-	-	-	-	-	-	-	
(0)AA9    Reserved	(0xA8)	Reserved	-	-	-	-	-	-	-	-	
(0xA5)   Reserved	(0xA7)	-	-	-	-	-	-	-	-	-	
(0)A43    Reserved				ļ		-	-		-	-	
(0xA2)   Reserved   -	· · · · · ·		-						-	-	
(0)A2)   Reserved	· · · · · ·	-		-	-	-	-	-	-	-	
(0xA1)   Reserved										-	
(0x86)   Reserved	· · · · · ·									1	
(0x96)   Reserved   -	<del></del>									+	
(0x96)   Reserved   -   -   -   -   -   -   -   -   -											
(0x90C)   Reserved						-					1
(0x9G)   Reserved   -   -						_				+	
(0x9B)   OCR3BH				ļ		1					
(0x9A)   OCR3BL	, ,						Output Compare	Register B High Byte <sup>(7)</sup>			132
(0x99)   OCR3AH											+
(0x97)   ICR3H											
(0x96)   ICR3L	(0x98)	OCR3AL			7	Fimer/Counter3 - C	Output Compare	Register A Low Byte <sup>(7)</sup>			132
Cox95	(0x97)	ICR3H				Timer/Counter3	- Input Capture F	Register High Byte <sup>(7)</sup>			133
(0x94)   TCNT3L	(0x96)	ICR3L				Timer/Counter3	- Input Capture I	Register Low Byte <sup>(7)</sup>			133
(0x93)	(0x95)	TCNT3H				Timer/Counte	r3 - Counter Reç	gister High Byte <sup>(7)</sup>			132
(0x92)   TCCR3C   FOC3A   FOC3B   -	(0x94)	TCNT3L				Timer/Counte	er3 - Counter Re	gister Low Byte <sup>(7)</sup>			132
(0x91)   TCCR3B   ICNC3   ICES3   -   WGM33   WGM32   CS32   CS31   CS30   130     (0x90)   TCCR3A   COM3A1   COM3A0   COM3B1   COM3B0   -					-	-	-	-	-	-	
(0x90)   TCCR3A   COM3A1   COM3A0   COM3B1   COM3B0   -   -   WGM31   WGM30   128							-				
(0x8F)   Reserved   -   -   -   -   -   -   -   -   -			1							+	+
(0x8E)         Reserved         -         <		1									128
(0x8D)         Reserved         -         <											
(0x8C)         Reserved         -         <				-	-					-	
(0x8B)   OCR1BH   Timer/Counter1 - Output Compare Register B High Byte   132	<u> </u>	1		-	-	-	1			-	
(0x8A)         OCR1BL         Timer/Counter1 - Output Compare Register B Low Byte         132           (0x89)         OCR1AH         Timer/Counter1 - Output Compare Register A High Byte         132           (0x88)         OCR1AL         Timer/Counter1 - Output Compare Register A Low Byte         132           (0x87)         ICR1H         Timer/Counter1 - Input Capture Register High Byte         133           (0x86)         ICR1L         Timer/Counter1 - Input Capture Register Low Byte         133           (0x85)         TCNT1H         Timer/Counter1 - Counter Register High Byte         132           (0x84)         TCNT1L         Timer/Counter1 - Counter Register Low Byte         132           (0x83)         Reserved         -         -         -         -         -           (0x82)         TCCR1C         FOC1A         FOC1B         -         -         -         -         -         131           (0x81)         TCCR1B         ICNC1         ICES1         -         WGM13         WGM12         CS12         CS11         CS10         130           (0x80)         TCCR1A         COM1A1         COM1B0         -         -         AIN1D         AIN1D         AIN0D         234           (0x7F)         DIDR0 <td< td=""><td></td><td></td><td>-</td><td>-</td><td></td><td></td><td></td><td></td><td>-</td><td>-</td><td>122</td></td<>			-	-					-	-	122
(0x89)   OCR1AH   Timer/Counter1 - Output Compare Register A High Byte   132											+
(0x88)         OCR1AL         Timer/Counter1 - Output Compare Register A Low Byte         132           (0x87)         ICR1H         Timer/Counter1 - Input Capture Register High Byte         133           (0x86)         ICR1L         Timer/Counter1 - Input Capture Register Low Byte         133           (0x85)         TCNT1H         Timer/Counter1 - Counter Register High Byte         132           (0x84)         TCNT1L         Timer/Counter1 - Counter Register Low Byte         132           (0x83)         Reserved         -         -         -         -         -           (0x82)         TCCR1C         FOC1A         FOC1B         -         -         -         -         -         131           (0x81)         TCCR1B         ICNC1         ICES1         -         WGM13         WGM12         CS12         CS11         CS10         130           (0x80)         TCCR1A         COM1A1         COM1A0         COM1B0         -         -         WGM11         WGM10         128           (0x7F)         DIDR1         -         -         -         -         ADC4D         ADC3D         ADC2D         ADC1D         ADC0D         253			<del> </del>					,			
(0x87)   ICR1H   Timer/Counter1 - Input Capture Register High Byte   133		-									_
(0x86)   ICR1L   Timer/Counter1 - Input Capture Register Low Byte   133											+
(0x85)   TCNT1H   Timer/Counter1 - Counter Register High Byte   132											
(0x84)   TCNT1L		+							+		
(0x83)         Reserved         -         <											+
(0x82)         TCCR1C         FOC1A         FOC1B         -         -         -         -         -         -         131           (0x81)         TCCR1B         ICNC1         ICES1         -         WGM13         WGM12         CS12         CS11         CS10         130           (0x80)         TCCR1A         COM1A1         COM1A0         COM1B1         COM1B0         -         -         WGM11         WGM10         128           (0x7F)         DIDR1         -         -         -         -         AIN1D         AIN0D         234           (0x7E)         DIDR0         ADC7D         ADC6D         ADC5D         ADC4D         ADC3D         ADC2D         ADC1D         ADC0D         253			-	-	-			ř – – – – – – – – – – – – – – – – – – –	-	-	
(0x80)         TCCR1A         COM1A1         COM1A0         COM1B1         COM1B0         -         -         WGM11         WGM10         128           (0x7F)         DIDR1         -         -         -         -         -         -         AIN1D         AIN0D         234           (0x7E)         DIDR0         ADC7D         ADC6D         ADC5D         ADC4D         ADC3D         ADC2D         ADC1D         ADC0D         253			FOC1A	FOC1B	-	-	-	-	-	-	131
(0x7F)         DIDR1         -         -         -         -         -         AIN1D         AIN0D         234           (0x7E)         DIDR0         ADC7D         ADC6D         ADC5D         ADC4D         ADC3D         ADC2D         ADC1D         ADC0D         253			ICNC1	ICES1	-	WGM13	WGM12	CS12	CS11	CS10	130
(0x7E) DIDRO ADC7D ADC6D ADC5D ADC4D ADC3D ADC2D ADC1D ADC0D 253	(0x80)	TCCR1A	COM1A1	COM1A0	COM1B1	COM1B0	-	-	WGM11	WGM10	128
	(0x7F)	DIDR1	-	-	-		-	-	AIN1D	AIN0D	234
(0x7D) Reserved	(0x7E)	DIDR0	ADC7D	ADC6D	ADC5D	ADC4D	ADC3D	ADC2D	ADC1D	ADC0D	253
	(0x7D)	Reserved	-	-	-	-	-	-	-	-	



Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Page
(0x7C)	ADMUX	REFS1	REFS0	ADLAR	MUX4	MUX3	MUX2	MUX1	MUX0	249
(0x7B)	ADCSRB	-	ACME	-	-	-	ADTS2	ADTS1	ADTS0	233
(0x7A)	ADCSRA	ADEN	ADSC	ADATE	ADIF	ADIE	ADPS2	ADPS1	ADPS0	250
(0x79)	ADCH			•	ADC	Data Register F	ligh byte		•	251
(0x78)	ADCL				ADC	Data Register L	ow byte			251
(0x77)	Reserved	-	-	-	-	-	-	-	-	
(0x76)	Reserved	-	-	-	-	-	-	-	-	
(0x75)	Reserved	-	-	-	-	-	-	-	-	
(0x74)	Reserved	-	-	-	-	-	-	-	-	
(0x73)	PCMSK3	PCINT31	PCINT30	PCINT29	PCINT28	PCINT27	PCINT26	PCINT25	PCINT24	70
(0x72)	Reserved	-	-	-	-	-	-	-	-	
(0x71)	TIMSK3	-	-	ICIE3	-	-	OCIE3B	OCIE3A	TOIE3	134
(0x70)	TIMSK2	-	-	-	-	-	OCIE2B	OCIE2A	TOIE2	156
(0x6F)	TIMSK1	-	-	ICIE1	-	-	OCIE1B	OCIE1A	TOIE1	134
(0x6E)	TIMSK0 PCMSK2	PCINT23	PCINT22	PCINT21	PCINT20	PCINT19	OCIE0B PCINT18	OCIE0A	TOIE0 PCINT16	105 70
(0x6D)	PCMSK1	PCINT23 PCINT15	PCINT22 PCINT14	PCINT21 PCINT13	PCINT20 PCINT12	PCINT 19 PCINT11	PCINT 16 PCINT 10	PCINT17 PCINT9	PCINT 16 PCINT8	70
(0x6C) (0x6B)	PCMSK0	PCINT7	PCINT 14	PCINT 13	PCINT12 PCINT4	PCINT11	PCINT2	PCINT9	PCINT0	71
(0x6A)	Reserved	-	-	-	-		-	-	-	/ 1
(0x69)	EICRA	-	-	ISC21	ISC20	ISC11	ISC10	ISC01	ISC00	67
(0x68)	PCICR	-	-	-	-	PCIE3	PCIE2	PCIE1	PCIE0	69
(0x67)	Reserved	-	-	-	-	-	-	-	-	
(0x66)	OSCCAL					lator Calibration				40
(0x65)	PRR1	-	-	-	-	-	-	-	PRTIM3	49
(0x64)	PRR0	PRTWI	PRTIM2	PRTIM0	PRUSART1	PRTIM1	PRSPI	PRUSART0	PRADC	48
(0x63)	Reserved	-	-	-	-	-	-	-	-	
(0x62)	Reserved	-	-	-	-	-	-	-	-	
(0x61)	CLKPR	CLKPCE	-	-	-	CLKPS3	CLKPS2	CLKPS1	CLKPS0	40
(0x60)	WDTCSR	WDIF	WDIE	WDP3	WDCE	WDE	WDP2	WDP1	WDP0	59
0x3F (0x5F)	SREG	1	T	Н	S	V	N	Z	С	11
0x3E (0x5E)	SPH	SP15	SP14	SP13	SP12	SP11	SP10	SP9	SP8	12
0x3D (0x5D)	SPL	SP7	SP6	SP5	SP4	SP3	SP2	SP1	SP0	12
0x3C (0x5C)	Reserved	-	-	-	-	-	-	-	-	
0x3B (0x5B)	Reserved	-	-	-	-	-	-	-	-	
0x3A (0x5A)	Reserved	-	-	-	-	-	-	-	-	
0x39 (0x59)	Reserved	-	-	-	-	-	-	-	-	
0x38 (0x58)	Reserved	-	-	-	-	-	- POWET	-	-	005
0x37 (0x57)	SPMCSR	SPMIE -	RWWSB	SIGRD	RWWSRE	BLBSET	PGWRT -	PGERS -	SPMEN	285
0x36 (0x56) 0x35 (0x55)	Reserved MCUCR	JTD	BODS <sup>(6)</sup>	BODSE <sup>(6)</sup>	PUD	-	-	IVSEL	IVCE	89/268
0x33 (0x53) 0x34 (0x54)	MCUSR	-	-	-	JTRF	WDRF	BORF	EXTRF	PORF	58/268
0x34 (0x54) 0x33 (0x53)	SMCR	-	-	-	JIKF	SM2	SM1	SM0	SE	47
0x33 (0x53)	Reserved	-	-	-	-	- SIVIZ	-	-	- -	47
0x31 (0x51)	OCDR					n-Chip Debug Re				259
0x30 (0x50)	ACSR	ACD	ACBG	ACO	ACI	ACIE	ACIC	ACIS1	ACIS0	250
0x2F (0x4F)	Reserved	-	-	-	-	-	-	-	-	200
0x2E (0x4E)	SPDR					SPI 0 Data Regi	ister			166
0x2D (0x4D)	SPSR	SPIF0	WCOL0	-	-	-	-	-	SPI2X0	165
0x2C (0x4C)	SPCR	SPIE0	SPE0	DORD0	MSTR0	CPOL0	CPHA0	SPR01	SPR00	164
0x2B (0x4B)	GPIOR2			•		ral Purpose I/O F	•		•	29
0x2A (0x4A)	GPIOR1					ral Purpose I/O F	-			29
0x29 (0x49)	Reserved	-	-	-	-	-	-	-	-	
0x28 (0x48)	OCR0B				Timer/Coun	ter0 Output Com	pare Register B			105
0x27 (0x47)	OCR0A				Timer/Coun	ter0 Output Com	npare Register A			105
0x26 (0x46)	TCNT0					imer/Counter0 (	8 Bit)			105
0x25 (0x45)	TCCR0B	FOC0A	FOC0B	-	-	WGM02	CS02	CS01	CS00	104
0x24 (0x44)	TCCR0A	COM0A1	COM0A0	COM0B1	COM0B0	-	-	WGM01	WGM00	105
0x23 (0x43)	GTCCR	TSM	-	-	-	-	-	PSRASY	PSRSYNC	157
0x22 (0x42)	EEARH	-	-	-	-	<u> </u>		ss Register High Byte		24
0x21 (0x41)	EEARL					Address Regis	-			24
0x20 (0x40)	EEDR			1	1	EPROM Data Re		T	Г	24
0x1F (0x3F)	EECR	-	-	EEPM1	EEPM0	EERIE	EEMPE	EEPE	EERE	24
0x1E (0x3E)	GPIOR0				Gene	ral Purpose I/O F		· · · - ·		29
0x1D (0x3D)	EIMSK	-	-	-	-	-	INT2	INT1	INTO	68
0x1C (0x3C)	EIFR	-	-	-	-	- DOIT2	INTF2	INTF1	INTF0	68
0x1B (0x3B)	PCIFR	-	-	-	-	PCIF3	PCIF2	PCIF1	PCIF0	69
0x1A (0x3A)	Reserved	-	-	-	-	-	-	-	-	-
0x19 (0x39)	Reserved	-	-	-	-	-	-	-	-	1



Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Page
0x18 (0x38)	TIFR3	-	-	ICF3	-	-	OCF3B	OCF3A	TOV3	136
0x17 (0x37)	TIFR2	-	-	-	-	-	OCF2B	OCF2A	TOV2	156
0x16 (0x36)	TIFR1	-	-	ICF1	-	-	OCF1B	OCF1A	TOV1	135
0x15 (0x35)	TIFR0	-	-	-	-	-	OCF0B	OCF0A	TOV0	106
0x14 (0x34)	Reserved	-	-	-	-	-	-	-	-	
0x13 (0x33)	Reserved	-	-	-	-	-	-	-	-	
0x12 (0x32)	Reserved	-	-	-	-	-	-	-	-	
0x11 (0x31)	Reserved	-	-	-	-	-	-	-	-	
0x10 (0x30)	Reserved	-	-	-	-	-	-	-	-	
0x0F (0x2F)	Reserved	-	-	-	-	-	-	-	-	
0x0E (0x2E)	Reserved	-	-	-	-	-	-	-	-	
0x0D (0x2D)	Reserved	-	-	-	-	-	-	-	-	
0x0C (0x2C)	Reserved	-	-	-	-	-	-	-	-	
0x0B (0x2B)	PORTD	PORTD7	PORTD6	PORTD5	PORTD4	PORTD3	PORTD2	PORTD1	PORTD0	90
0x0A (0x2A)	DDRD	DDD7	DDD6	DDD5	DDD4	DDD3	DDD2	DDD1	DDD0	90
0x09 (0x29)	PIND	PIND7	PIND6	PIND5	PIND4	PIND3	PIND2	PIND1	PIND0	90
0x08 (0x28)	PORTC	PORTC7	PORTC6	PORTC5	PORTC4	PORTC3	PORTC2	PORTC1	PORTC0	90
0x07 (0x27)	DDRC	DDC7	DDC6	DDC5	DDC4	DDC3	DDC2	DDC1	DDC0	90
0x06 (0x26)	PINC	PINC7	PINC6	PINC5	PINC4	PINC3	PINC2	PINC1	PINC0	90
0x05 (0x25)	PORTB	PORTB7	PORTB6	PORTB5	PORTB4	PORTB3	PORTB2	PORTB1	PORTB0	89
0x04 (0x24)	DDRB	DDB7	DDB6	DDB5	DDB4	DDB3	DDB2	DDB1	DDB0	89
0x03 (0x23)	PINB	PINB7	PINB6	PINB5	PINB4	PINB3	PINB2	PINB1	PINB0	90
0x02 (0x22)	PORTA	PORTA7	PORTA6	PORTA5	PORTA4	PORTA3	PORTA2	PORTA1	PORTA0	89
0x01 (0x21)	DDRA	DDA7	DDA6	DDA5	DDA4	DDA3	DDA2	DDA1	DDA0	89
0x00 (0x20)	PINA	PINA7	PINA6	PINA5	PINA4	PINA3	PINA2	PINA1	PINA0	89

Notes: 1. For compatibility with future devices, reserved bits should be written to zero if accessed. Reserved I/O memory addresses should never be written.

- 2. I/O registers within the address range \$00 \$1F are directly bit-accessible using the SBI and CBI instructions. In these registers, the value of single bits can be checked by using the SBIS and SBIC instructions.
- 3. Some of the status flags are cleared by writing a logical one to them. Note that the CBI and SBI instructions will operate on all bits in the I/O register, writing a one back into any flag read as set, thus clearing the flag. The CBI and SBI instructions work with registers 0x00 to 0x1F only.
- 4. When using the I/O specific commands IN and OUT, the I/O addresses \$00 \$3F must be used. When addressing I/O registers as data space using LD and ST instructions, \$20 must be added to these addresses. The ATmega164A/164PA/324A/324PA/644A/644PA/1284/1284P is a complex microcontroller with more peripheral units than can be supported within the 64 location reserved in Opcode for the IN and OUT instructions. For the Extended I/O space from \$60 \$FF, only the ST/STS/STD and LD/LDS/LDD instructions can be used.
- 5. USART in SPI Master Mode.
- 6. Only available in the ATmega164PA/324PA/644PA/1284P.
- 7. Only available in the ATmega1284/1284P



Mnemonics	Operands	Operands Description O		Flags	#Clocks	
MCU CONTROL INSTRUCTIONS						
NOP		No Operation		None	1	
SLEEP		Sleep	(see specific descr. for Sleep function)	None	1	
WDR		Watchdog Reset	(see specific descr. for WDR/timer)	None	1	
BREAK		Break	For On-chip Debug Only	None	N/A	



#### **Atmel ATmega164PA** 9.2

Speed [MHz] (3)	Power supply	Ordering code (2)	Package <sup>(1)</sup>	Operational range
20	1.8 - 5.5V	ATmega164PA-AU ATmega164PA-AUR <sup>(5)</sup> ATmega164PA-PU ATmega164PA-MU ATmega164PA-MUR <sup>(5)</sup> ATmega164PA-MCH <sup>(4)</sup> ATmega164PA-MCHR <sup>(4)</sup> ATmega164PA-CU ATmega164PA-CU	44A 44A 40P6 44M1 44M1 44MC 44MC 49C2 49C2	Industrial (-40°C to 85°C)
20	1.8 - 5.5V	ATmega164PA-AN ATmega164PA-ANR <sup>(5)</sup> ATmega164PA-PN ATmega164PA-MN ATmega164PA-MNR <sup>(5)</sup>	44A 44A 40P6 44M1 44M1	Industrial (-40°C to 105°C)

- Notes: 1. This device can also be supplied in wafer form. Please contact your local Atmel sales office for detailed ordering information and minimum quantities.
  - 2. Pb-free packaging, complies to the European Directive for Restriction of Hazardous Substances (RoHS directive). Also Halide free and fully Green.
  - 3. For Speed vs. V<sub>CC</sub> see "Speed grades" on page 324.
  - 4. NiPdAu Lead Finish.
  - 5. Tape & Reel.

	Package Type
44A	44-lead, Thin (1.0mm) Plastic Gull Wing Quad Flat Package (TQFP)
40P6	40-pin, 0.600" Wide, Plastic Dual Inline Package (PDIP)
44M1	44-pad, 7 × 7 × 1.0mm body, lead pitch 0.50mm, Thermally Enhanced Plastic Very Thin Quad Flat No-Lead (VQFN)
44MC	44-lead (2-row Staggered), 5 × 5 × 1.0mm body, 2.60 × 2.60mm Exposed Pad, Quad Flat No-Lead Package (QFN)
49C2	49-ball, (7 × 7 Array) 0.65mm Pitch, 5 × 5 × 1mm, Very Thin, Fine-Pitch Ball Grid Array Package (VFBGA)



# 9.3 Atmel ATmega324A

Speed [MHz] (3)	Power supply	Ordering code (2)	Package (1)	Operational range
20	1.8 - 5.5V	ATmega324A-AU ATmega324A-AUR <sup>(5)</sup> ATmega324A-PU ATmega324A-MU ATmega324A-MUR <sup>(5)</sup> ATmega324A-MCH <sup>(4)</sup> ATmega324A-MCHR <sup>(4)(5)</sup> ATmega324A-CU ATmega324A-CUR <sup>(5)</sup>	44A 44A 40P6 44M1 44M1 44MC 44MC 49C2 49C2	Industrial (-40°C to 85°C)

Notes: 1. This device can also be supplied in wafer form. Please contact your local Atmel sales office for detailed ordering information and minimum quantities.

- 2. Pb-free packaging, complies to the European Directive for Restriction of Hazardous Substances (RoHS directive). Also Halide free and fully Green.
- 3. For Speed vs.  $V_{CC}$  see "Speed grades" on page 324.
- 4. NiPdAu Lead Finish.
- 5. Tape & Reel.

	Package Type
44A	44-lead, Thin (1.0mm) Plastic Gull Wing Quad Flat Package (TQFP)
40P6	40-pin, 0.600" Wide, Plastic Dual Inline Package (PDIP)
44M1	44-pad, 7 × 7 × 1.0mm body, lead pitch 0.50mm, Thermally Enhanced Plastic Very Thin Quad Flat No-Lead (VQFN)
44MC	44-lead (2-row Staggered), 5 × 5 × 1.0mm body, 2.60 × 2.60mm Exposed Pad, Quad Flat No-Lead Package (QFN)
49C2	49-ball, (7 × 7 Array) 0.65mm Pitch, 5 × 5 × 1mm, Very Thin, Fine-Pitch Ball Grid Array Package (VFBGA)



#### Atmel ATmega644PA 9.6

Speed [MHz] (3)	Power supply	Ordering code (2)	Package (1)	Operational range
20	1.8 - 5.5V	ATmega644PA-AU ATmega644PA-AUR <sup>(4)</sup> ATmega644PA-PU ATmega644PA-MU ATmega644PA-MUR <sup>(4)</sup>	44A 44A 40P6 44M1 44M1	Industrial (-40°C to 85°C)
20	1.8 - 5.5V	ATmega644PA-AN ATmega644PA-ANR <sup>(4)</sup> ATmega644PA-PN ATmega644PA-MN ATmega644PA-MNR <sup>(4)</sup>	44A 44A 40P6 44M1 44M1	Industrial (-40°C to 105°C)

- Notes: 1. This device can also be supplied in wafer form. Please contact your local Atmel sales office for detailed ordering information and minimum quantities.
  - 2. Pb-free packaging, complies to the European Directive for Restriction of Hazardous Substances (RoHS directive). Also Halide free and fully Green.
  - 3. For Speed vs.  $V_{CC}$  see "Speed grades" on page 324.
  - 4. Taper & Reel.

Package Type			
44A	44-lead, Thin (1.0mm) Plastic Gull Wing Quad Flat Package (TQFP)		
40P6	40-pin, 0.600" Wide, Plastic Dual Inline Package (PDIP)		
44M1	44-pad, 7 × 7 × 1.0mm body, lead pitch 0.50mm, Thermally Enhanced Plastic Very Thin Quad Flat No-Lead (VQFN)		



#### Atmel ATmega1284P 9.8

Speed [MHz] (3)	Power supply	Ordering code (2)	Package (1)	Operational range
20	1.8 - 5.5V	ATmega1284P-AU ATmega1284P-AUR <sup>(4)</sup> ATmega1284P-PU ATmega1284P-MU ATmega1284P-MUR <sup>(4)</sup>	44A 44A 40P6 44M1 44M1	Industrial (-40°C to 85°C)
20	1.8 - 5.5V	ATmega1284P-AN ATmega1284P-ANR <sup>(4)</sup> ATmega1284P-PN ATmega1284P-MN ATmega1284P-MNR <sup>(4)</sup>	44A 44A 40P6 44M1 44M1	Industrial (-40°C to 105°C)


- Notes: 1. This device can also be supplied in wafer form. Please contact your local Atmel sales office for detailed ordering information and minimum quantities.
  - 2. Pb-free packaging, complies to the European Directive for Restriction of Hazardous Substances (RoHS directive). Also Halide free and fully Green.
  - 3. For Speed vs.  $V_{CC}$  see "Speed grades" on page 324.
  - 4. Tape & Reel.

Package Type			
44A	44-lead, Thin (1.0mm) Plastic Gull Wing Quad Flat Package (TQFP)		
40P6	40-pin, 0.600" Wide, Plastic Dual Inline Package (PDIP)		
44M1	44-pad, 7 × 7 × 1.0mm body, lead pitch 0.50mm, Quad Flat No-Lead/Micro Lead Frame Package (QFN/MLF)		



# 10. Packaging information

### 10.1 44A





# COMMON DIMENSIONS

(Unit of Measure = mm)

(Orm or modears man)					
SYMBOL	MIN	NOM	MAX	NOTE	
Α	_	_	1.20		
A1	0.05	_	0.15		
A2	0.95	1.00	1.05		
D	11.75	12.00	12.25		
D1	9.90	10.00	10.10	Note 2	
E	11.75	12.00	12.25		
E1	9.90	10.00	10.10	Note 2	
В	0.30	0.37	0.45		
С	0.09	(0.17)	0.20		
L	0.45	0.60	0.75		
е		0.80 TYP			

#### Notes


- 1. This package conforms to JEDEC reference MS-026, Variation ACB.
- Dimensions D1 and E1 do not include mold protrusion. Allowable protrusion is 0.25mm per side. Dimensions D1 and E1 are maximum plastic body size dimensions including mold mismatch.
- 3. Lead coplanarity is 0.10mm maximum.


06/02/2014


	TITLE	DRAWING NO.	REV.
Atmel Package Drawing Contact:  packagedrawings@atmel.com	<b>44A</b> , 44-lead, 10 x 10mm body size, 1.0mm body thickness, 0.8 mm lead pitch, thin profile plastic quad flat package (TQFP)	44A	С



# 10.2 40P6







# **COMMON DIMENSIONS**

(Unit of Measure = mm)

SYMBOL	MIN	NOM	MAX	NOTE
А	_	-	4.826	
A1	0.381	_	_	
D	52.070	1	52.578	Note 2
E	15.240	_	15.875	
E1	13.462	_	13.970	Note 2
В	0.356	_	0.559	
B1	1.041	_	1.651	
L	3.048	_	3.556	
С	0.203	_	0.381	
eB	15.494	-	17.526	
е		2.540 TYP	)	

#### Notes:


- 1. This package conforms to JEDEC reference MS-011, Variation AC.
- 2. Dimensions D and E1 do not include mold Flash or Protrusion. Mold Flash or Protrusion shall not exceed 0.25mm (0.010").

13/02/2014

	TITLE	DRAWING NO.	REV.
Atmel Package Drawing Contact:  packagedrawings@atmel.com	<b>40P6</b> , 40-lead (0.600"/15.24mm Wide) Plastic Dual Inline Package (PDIP)	40P6	С




### 10.3 44M1





### 10.5 49C2





# 11. Errata

# 11.1 Errata for ATmega164A

#### 11.1.1 Rev. E

No known Errata.

# 11.2 Errata for ATmega164PA

#### 11.2.1 Rev. E

No known Errata.

# 11.3 Errata for ATmega324A

#### 11.3.1 Rev. F

No known Errata.

# 11.4 Errata for ATmega324PA

#### 11.4.1 Rev. F

No known Errata.

# 11.5 Errata for ATmega644A

#### 11.5.1 Rev. F

No known Errata.

# 11.6 Errata for ATmega644PA

#### 11.6.1 Rev. F

No known Errata.

# 11.7 Errata for ATmega1284

#### 11.7.1 Rev. B

No known Errata.

# 11.8 Errata for ATmega1284P

### 11.8.1 Rev. B

No known Errata.



# 12. Datasheet revision history

Please note that the referring page numbers in this section are referred to this document. The referring revision in this section are referring to the document revision.

#### 12.1 Rev. 8272G - 01/2015

- 1. Updated Table 1-2 on page 5, Table 8-1 on page 25, Table 10-1 on page 42, Table 14-3 on page 79, Table 19-4 on page 187, Table 19-11 on page 192 and Table 28-16 on page 328 for formatting consistency errors
  - Updated "Ordering information" on page 17:
- Added ordering information for ATmega164PA @105°C; ATmega324PA @ 105°C; ATmega324PA @105°C; ATmega644PA @ 105°C and ATmega1284P @ 105°C
- Updated the "Packaging information" on page 25:
  - Replaced the drawing "44M1" on page 27 by a correct package

#### 12.2 Rev. 8272F - 08/2014

- 1. Updated text in Section 13.2.8 "PCMSK1 Pin Change Mask Register 1" on page 70 to: "If PCINT15:8 is set and the PCIE1 bit in PCICR is set, pin change interrupt is enabled on the corresponding I/O pin."
- 2. Corrected description of PAGEMSB in Table 26-9 on page 281. The device has 64 words in a page and not 128.
- 3. Corrected description of PAGEMSB in Table 26-12 on page 282. PAGESMB is 5 and the device has 64 words in a page and not 128. The page require six bits and not seven.
- 4. Corrected values in Table 26-16 on page 284. PAGEMSB is 6. ZPAGEMSB is Z7 and PCPAGE is Z15:Z8
- 5. Corrected value for PCPAGE in Table 27-7 on page 290. The correct value is PC[14:7]
- 6. Updated description in Table 17-2 on page 151 to "Normal port operation, OC2A disconnected."
  - Updated Assembly code examples on for "Watchdog Timer" on page 55. and onwards
- 7. "out WDTCSR, r16" changed to "sts WDTCSR, r16" "in r16, WDTCSR" changed to "lds r16, WDTCSR" "idi r16, WDTCSR" changed to "lds r16, WDTCSR"
- 8. Updated addresses 0x65 and 0x64 in Section 7. "Register summary" on page 10.
- 9. Removed notes 5 and 6 from Table 28-16 on page 328.
- 10. Corrected values in Section 8. "Instruction set summary" on page 14. Changed clock values for RCALL and ICALL to 2, for Call, Ret and RETI to 4. Also changed values in Section 7.7.1 "Interrupt response time" on page 18.
- 11. Updated layout, footer and back page according to template 0205/2014



- 12. Added "OCR3AH and OCR3AL Output Compare Register3 A" on page 133
- 13. Added "OCR3BH and OCR3BL Output Compare Register3 B" on page 133
- 14. Added "TIMSK3 Timer/Counter3 Interrupt Mask Register" on page 134
- 15. Updated All "SPI Serial Peripheral Interface" "Register description" to reflect ATmega1284 and ATmega1284P.
- 16. Updated "Addressing the Flash During Self-Programming" on page 274 to include RAMPZ register.
- 17. Updated Table 27-16 on page 303. t<sub>WD\_EEPROM</sub> is 3.6ms instead of 9ms.
- 18. BODS and BODSE bits denoted as R/W
- 19. Description of external pin modes below table 16-9 removed.
- 20. Updated "Register summary" on page 10 to include Timer/Counter3.
- 21. Updated the datasheet with Atmel new style guide.

### 12.7 Rev. 8272A - 01/10

- 1. Initial revision (Based on the ATmega164PA/324PA/644PA/1284P datasheet 8252G-AVR-11/09 and on the ATmega644 datasheet 2593N-AVR-09/09).
- 2. Changes done:
  - Non-picoPower devices added: ATmega164A/324A/644A/1284
  - Updated Table 2-1 on page 7
  - Updated Table 10-1 on page 42
  - Updated "Sleep Modes" on page 42 and "BOD disable<sup>(1)</sup>" on page 43
  - Updated "Register description" on page 67
  - Updated "USART" on page 167 and "USART in SPI mode" on page 194
  - Updated "Signature Bytes" on page 290 and "Page Size" on page 290
  - Added "DC Characteristics" on page 318 for non-picoPower devices.
  - Added "Atmel ATmega164A typical characteristics" on page 333
  - Added "Atmel ATmega324A typical characteristics" on page 386
  - Added "Atmel ATmega644A typical characteristics" on page 438
  - Added "ATmega1284 typical characteristics" on page 490
  - Added "Ordering information" on page 17 for non-picoPower devices
  - Added "Errata for ATmega164A" on page 30
  - Added "Errata for ATmega324A" on page 30
  - Added "Errata for ATmega644PA" on page 30
  - Added "Errata for ATmega1284" on page 30











1600 Technology Drive, San Jose, CA 95110 USA T: (+1)(408) 441.0311 F: (+1)(408) 436.4200 **Atmel Corporation** www.atmel.com

© 2015 Atmel Corporation. / Rev.: Atmel-8272GS-AVR-ATmega164A/PA/324A/PA/644A/PA/1284/P-Datasheet Summary\_01/2015.

Atmel®, Atmel logo and combinations thereof, Enabling Unlimited Possibilities, and others are registered trademarks or trademarks of Atmel Corporation in U.S. and other countries. Other terms and product names may be trademarks of others.

DISCLAIMER: The information in this document is provided in connection with Atmel products. No license, express or implied, by estoppel or otherwise, to any intellectual property right is granted by this document or in connection with the sale of Atmel products. EXCEPT AS SET FORTH IN THE ATMEL TERMS AND CONDITIONS OF SALES LOCATED ON THE ATMEL WEBSITE, ATMEL ASSUMES NO LIABILITY WHATSOEVER AND DISCLAIMS ANY EXPRESS, IMPLIED OR STATUTORY WARRANTY RELATING TO ITS PRODUCTS INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTY OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE, OR NON-INFRINGEMENT. IN NO EVENT SHALL ATMEL BE LIABLE FOR ANY DIRECT, INDIRECT, CONSEQUENTIAL, PUNITIVE, SPECIAL OR INCIDENTAL DAMAGES (INCLUDING, WITHOUT LIMITATION, DAMAGES FOR LOSS AND PROFITS, BUSINESS INTERRUPTION, OR LOSS OF INFORMATION) ARISING OUT OF THE USE OR INABILITY TO USE THIS DOCUMENT, EVEN IF ATMEL HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES. Atmel makes no representations or warranties with respect to the accuracy or completeness of the contents of this document and reserves the right to make changes to specifications and products descriptions at any time without notice. Atmel does not make any commitment to update the information contained herein. Unless specifically provided otherwise, Atmel products are not suitable for, and shall not be used in, automotive applications. Atmel products are not intended, authorized, or warranted for use as components in applications intended to support or sustain life.

SAFETY-CRITICAL, MILITARY, AND AUTOMOTIVE APPLICATIONS DISCLAIMER: Atmel products are not designed for and will not be used in connection with any applications where the failure of such products would reasonably be expected to result in significant personal injury or death ("Safety-Critical Applications") without an Atmel officer's specific written consent. Safety-Critical Applications include, without limitation, life support devices and systems, equipment or systems for the operation of nuclear facilities and weapons systems. Atmel products are not designed nor intended for use in military or aerospace applications or environments unless specifically designated by Atmel as military-grade. Atmel products are not designed nor intended for use in automotive applications unless specifically designated by Atmel as automotive-grade.